

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT

Through e-mail

No.: -PW-E-in-C(P)/SOR/2019- 555-630

Dated:- 21/06/2019

To

The Engineer-in-Chief  
HPPWD, Nirman Bhawan,  
Shimla-2.

All the Zonal Chief Engineers  
in HPPWD.....

All the Superintending Engineers  
in HPPWD, .....

All the Executive Engineer  
in HPPWD,.....

**Subject:- Discontinuation of plum in Cement concrete work of Retaining walls & Breast walls.**

Due to non availability of proper size of plum being used in construction of R/walls and B/walls and there is no proper check on the quantum of plum used, it has been decided to discontinue the use of plum in the construction of R/wall, B/wall and parapet for ensuring quality of work.

Henceforth the following items will be used in the construction of Retaining walls, Breast wall.

Item No. as per HPSR 2009.	Description of items to be discontinued	Item No. as per HPSR 2009	Description of items to be used
11.14	Providing and Laying cement concrete 1:5:10 with 15% plums and curing complete including the cost of formwork for plain/reinforced concrete in retaining walls, breast walls, the size of plum should be 150 to 300mm as per drawing and HPPWD technical specifications	11.12	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203. P.C.C. nominal mix 1:5:10 (40 mm aggregates)

11.15	Providing and Laying cement concrete 1:4:8 with 15% plums and curing complete including the cost of formwork for plain/reinforced concrete in retaining walls, breast walls, the size of plum should be 150 to 300 mm as per drawing and HPPWD technical specifications.	11.11	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203. P.C.C. nominal mix 1:4:8 (25 mm aggregates)
-------	--	-------	---

In future all estimates and DNIT should be prepared accordingly.

1  
Engineer-in-Chief (Projects),  
HP.PWD, Nirman Bhawan, Shimla-2.

✓ Copy forwarded to Nodal Officer IT HPPWD, Nirman Bhawan, Shimla-2 with direction to upload the above on HPPWD website.

*Shimla*  
Engineer-in-Chief (Projects),  
HP.PWD, Nirman Bhawan, Shimla-2.